



Leverington Church Parvis Roof Renovation



We were asked to tender for the work required to the Parvis at Leverington Church and were happy when we were awarded the contract by Archimage Architects.

Scaffolding was erected to the East & West slopes of the Parvis, together with a temporary roof.

We carefully removed all the old stone slates after clearly marking their locations and replaced with new Clipsham Stone, finishing with new code 7 sand cast Lead flashings and cover flashings.

Specifically designed stainless steel support bars and brackets were installed to strengthen the stone roof trusses.

The roof trusses were repaired and all open joints pointed up with lime mortar.

